GENERAL NOTES:

A. CONTRACTOR TO UTILIZE EXISTING LIGHTING CIRCUITS TO PROVIDE SWITCHING PATTERNS AS SHOWN. VERIFY MAXIMUM OF 16A PER CIRCUIT. UPDATE PANEL DIRECTORY WHEN WORK IS COMPLETED.

B. CONTRACTOR TO ROUTE ALL LIGHTING WITHIN CORRIDORS, GARAGES, OPEN OFFICE AREAS AND ANY SPACE NOT CONTROLLED VIA OCCUPANCY SENSORS THRU TIMECLOCK/LIGHTING CONTROL PANEL FOR TIME OF DAY CONTROL. MATCH BUILDING STANDARD. IF NO STANDARD IS ESTABLISHED, INSTALL ACUITY #NDTC OR EQUIVALENT.

C. CONTRACTOR TO INSTALL OCCUPANCY SENSOR SWITCH WITH 0-10V DIMMING ($os) AS SHOWN. MATCH BUILDING STANDARD. IF NO STANDARD IS ESTABLISHED, INSTALL ACUITY #NWSXA-PDT-DX OR EQUIVALENT. NON-DIMMING TYPE IS ACCEPTABLE WITHIN STORAGE/BOH SPACES WHERE ACCEPTABLE TO ARCHITECT/OWNER. COORDINATE FINISH WITH ARCHITECT. SENSOR TO BE CONFIGURED TO AUTO-ON TO 50% / AUTO OFF.

D. CONTRACTOR TO INSTALL OCCUPANCY / VACANCY SENSOR (os) AS SHOWN. MATCH BUILDING STANDARD. IF NO STANDARD IS ESTABLISHED, INSTALL ACUITY #NCM-PDT SERIES OR EQUIVALENT. COORDINATE FINISH WITH ARCHITECT. LOCATIONS SHOWN ARE APPROXIMATE. REFERENCE INSTALLATION MANUAL FOR OPTIMUM PLACEMENT OF SENSORS. PROVIDE LOW-VOLTAGE SWITCH FOR AUTO-ON TO 50% OPERATION, ACUITY #NPODMA-DX SERIES OR EQUIVALENT.

E. AT ALL LOCATIONS WHERE CEILING OCCUPANCY / VACANCY SENSORS ARE SHOWN TO BE USED IN CONJUNCTION WITH DIMMING, CONTRACTOR TO PROVIDE DIMMING POWER-PACKS AS REQUIRED WITH DIMMING ZONE OR PRESET STATIONS. MULTI-BUTTONS MAY BE USED AS INDICATED ON PLAN.

F. CONTRACTOR TO INSTALL DIMMING SWITCH ($D $3,D $4,D) AS SHOWN. MATCH BUILDING STANDARD. IF NO STANDARD IS ESTABLISHED, INSTALL ACUITY #NPODMA-DX SERIES OR EQUIVALENT. COORDINATE FINISH WITH ARCHITECT.

G. PER IECC 2021 – C408.3 – CONTRACTOR TO PROVIDE FUNCTIONAL TESTING OF LIGHTING CONTROLS TO COMPLY WITH C408.3.1 THROUGH C408.3.2.

H. CONNECT ALL EMERGENCY FIXTURES AND EXIT SIGNS TO EXISTING BASE BUILDING EMERGENCY CIRCUITS. VERIFY MAXIMUM OF 16A PER CIRCUIT. IF NO EMERGENCY CIRCUITS ARE PRESENT, INSTALL BATTERY PACKS IN ALL EMERGENCY FIXTURES AND EXIT SIGNS. WIRE AHEAD OF SWITCH.

I. CONTRACTOR TO COORDINATE EXACT SWITCHING PATTERNS, TYPE AND SWITCH LOCATIONS WITH ARCHITECT PRIOR TO INSTALLATION. LOWER CASE LETTERS INDICATE SWITCHING PATTERNS.

J. SWITCHED EMERGENCY FIXTURE. WIRE FIXTURE OR PROVIDE UL924 DEVICE SUCH THAT FIXTURE TURNS TO FULL BRIGHT UPON LOSS OF NORMAL POWER REGARDLESS OF SWITCH/DIMMER POSITION.

K. PROVIDE POWER/RELAY PACKS AS REQUIRED TO MEET THE CONTROLLED RECEPTACLE REQUIREMENTS PER IECC 2021. FIELD VERIFY FINAL QUANTITIES REQUIRED.

1 7TH LEVEL FLOOR PLAN - LIGHTING
SCALE: 1/8"=1'-0"

0 4' 8' 16' 24'
SCALE: 1/8"=1'-0"

SCHMIDT & STACY CONSULTING ENGINEERS, INC.
2900 CITYPLACE
2711 N. HASKELL AVE.
DALLAS, TEXAS 75204
214-874-0200
TEXAS REGISTRATION #F000521
PROJECT # 1809083

SLI GROUP, INC.
ARCHITECTURE | DESIGN | CONSTRUCTION
15810 PARK TEN PLACE, SUITE 300
HOUSTON, TEXAS 77084
713-465-4650
www.sligroup.com

© COPYRIGHT

PROSPERITY BANK®

PROSPERITY BANK - RENOVATION
5949 SHERRY LANE
7TH FLOOR
DALLAS, TEXAS 75225

Project Number : 25-8974-01

ISSUED FOR	DATE
ISSUED FOR CLIENT APPROVAL	
ISSUED FOR BIDDING	
ISSUED FOR PERMIT	02/23/2026
ISSUED FOR CONSTRUCTION	

REVISIONS

MARK	DESCRIPTION	DATE

The information, ideas, designs, details, layouts, techniques, features, arrangements, plans, sequences, dimensions, allowances, tolerances, conceptions, specifications, intentions, technology or embodiments, as illustrated, arranged, displayed, noted, recorded, indicated, represented, disclosed, evidenced, detailed or otherwise reduced to tangible form hereon, either expressly, inherently or by implication, are the confidential and proprietary information of SLI Design, Inc., and shall not be used for any purpose other than the specific project or undertaking identified on the drawing title block or legend for which they are and have been prepared by SLI Design, Inc. Any other reproduction, disclosure or use of any portion of the confidential and proprietary information of SLI Design, Inc., shall be a breach of the obligation of confidence created by the acceptance of this drawing from SLI Design, Inc. for a specific project or Contract. Any copying, duplicating, reproducing, utilization, alteration, modification, revision or change to this drawing, is expressly prohibited unless done with the prior written consent or approval of SLI Design, Inc., and shall not be undertaken without receipt of such prior written approval. This drawing is loaned by SLI Design, Inc., for the limited purpose of complying with a specific Contract. The drawing remains the property of SLI Design, Inc., and shall be returned upon request or completion of the contract, unless specifically authorized by Contract, under which it was loaned.

PRINT DATE: 02/23/2026

STATE OF TEXAS
MATTHEW E. DEEKE
104941
LICENSED
PROFESSIONAL ENGINEER
02/23/2026

DRAWING TITLE: 7TH LEVEL FLOOR PLAN - LIGHTING

DRAWN BY: Author
CHECKED BY:
APPROVED BY:

SHEET NO. EL2.07