ELECTRICAL LIGHTING GENERAL NOTES:

1. MEP SPECIFICATIONS SHALL APPLY TO ALL WORK SHOWN ON THIS DRAWING UNLESS OTHERWISE NOTED.
2. REFER TO THE ARCHITECTURAL REFLECTED CEILING PLAN FOR THE EXACT LOCATION OF ALL LIGHTING FIXTURES.
3. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF ALL JUNCTION BOXES IN THE JUNCTION BOX GRID AND AVAILABILITY OF ALL CIRCUITS INDICATED TO BE USED.
4. CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF ALL EXISTING EQUIPMENT PRIOR TO CONSTRUCTION. PROVIDE CIRCUIT TRACING AS REQUIRED TO DETERMINE CIRCUIT AVAILABILITY. PROVIDE A WRITTEN REPORT TO ENGINEER AND BUILDING MANAGEMENT SHOWING LIGHTING LOCATIONS AND CIRCUIT NUMBER USED.
5. ALL UNUSED WIRING IS TO BE REMOVED BACK TO SOURCE UNLESS NOTED OTHERWISE.
6. EGRESS AND EXIT LIGHT FIXTURES SHALL BE CONNECTED TO UNSWITCHED HOT CONDUCTOR WITH 2#10,1/2"C.
7. ALL LIGHTING FIXTURES, LAMPS AND EXIT SIGNS SHALL MATCH BANK STANDARD UNLESS OTHERWISE NOTED.
8. CONTRACTOR SHALL REFER TO BUILDING MANAGEMENT'S "RULES AND REGULATIONS" TO COMPLY WITH BUILDING STANDARDS.
9. LIGHTING FIXTURES SHALL BE PROTECTED TO COMPLY WITH THE BUILDING FLOOR/CEILING FIRE RATED ASSEMBLY.
10. FOR RETURN AIR PLENUMS, ALL MATERIALS LOCATED WITHIN A RETURN AIR PLENUM SHALL BE RATED AND APPROVED FOR INSTALLATION IN A RETURN AIR PLENUM.

FINAL FIRE ALARM PLANS WILL BE PREPARED AND SUBMITTED FOR PERMIT REVIEW AND APPROVAL UPON THE SELECTION OF THE FIRE ALARM SUBCONTRACTOR FOR THE PROJECT. SUBCONTRACTOR SHALL PROVIDE PRICING FOR A FULL AND COMPLETE SYSTEM. INCLUDE COSTS FOR ADDITIONAL DEVICES IF THE SUBCONTRACTOR DEEMS IT NECESSARY. GC SHALL ENSURE THAT ALL COSTS FOR ROUGH-IN OF DEVICES IS COORDINATED BETWEEN TRADES AND ACCOUNTED FOR IN THE BID.

ELECTRICAL POWER GENERAL NOTES:

1. MEP SPECIFICATIONS SHALL APPLY TO ALL WORK ON THIS DRAWING UNLESS OTHERWISE NOTED.
2. REFER TO ARCHITECT FOR EXACT HEIGHT AND LOCATION OF ALL FLOOR AND WALL OUTLETS.
3. ALL DATA/TELEPHONE OUTLETS SHALL BE PROVIDED WITH PULL STRINGS.
4. CONTRACTOR SHALL LOCATE ALL ELECTRICAL & TELEPHONE OUTLETS WITHIN THE LIMITS OF THE TENANT FURNITURE PLAN PROVIDED BY THE ARCHITECT. CONTRACTOR SHALL MARK INTENDED LOCATION OF ALL OUTLETS PRIOR TO INSTALLATION, THEN SHALL NOTIFY TENANT FOR APPROVAL BEFORE PROCEEDING.
5. CONTRACTOR SHALL PROVIDE NEW CIRCUIT DIRECTORY CARD AT PANELS. CIRCUITS SHALL BE LABELED TO CORRESPOND TO THE CIRCUITS SHOWN ON THE DRAWINGS. CONTRACTOR SHALL CONNECT CIRCUITS AS REQUIRED TO COMPLY WITH THIS DRAWING.
6. CONDUCTORS SHALL BE #12 AWG SOLID COPPER (THWN) IN 1/2" CONDUIT UNLESS OTHERWISE INDICATED.
7. ALL OUTLETS TO BE MOUNTED VERTICALLY UNLESS OTHERWISE INDICATED.
8. CONTRACTOR SHALL PROVIDE ONE PULL STRING FOR EACH VOICE OR DATA OUTLET SHOWN. WHEN VOICE AND DATA OUTLETS ARE SHOWN ADJACENT, CONTRACTOR SHALL PROVIDE ONE PULL STRING (WITH ONE WALL PENETRATION) FOR THE PAIR, UNLESS NOTED OTHERWISE. VOICE AND DATA LINES SHALL BE PULLED BY OTHERS.
9. CONTRACTOR SHALL REFER TO BUILDING MANAGEMENT'S "RULES AND REGULATIONS" TO COMPLY WITH BUILDING STANDARDS.
10. GANG TOGETHER, ALL NEW ELECTRICAL, TELEPHONE AND COMPUTER OUTLETS SHOWN ADJACENT TO EACH OTHER.
11. VERIFY FINAL LOCATIONS FOR ROUGH-INS WITH FIELD MEASUREMENTS AND WITH THE REQUIREMENTS OF THE ACTUAL EQUIPMENT TO BE CONNECTED.
12. COORDINATE THE INSTALLATION OF ELECTRICAL MATERIALS AND EQUIPMENT ABOVE CEILINGS WITH SUSPENSION SYSTEM, MECHANICAL EQUIPMENT AND SYSTEMS, AND STRUCTURAL COMPONENTS. COORDINATE ELECTRICAL EQUIPMENT AND MATERIALS INSTALLATION WITH OTHER BUILDING COMPONENTS.
13. VERIFY MECHANICAL EQUIPMENT SWITCH AND CONNECTION REQUIREMENTS, ITEM BY ITEM, WITH THE MECHANICAL CONTRACTOR, BEFORE WIRING EQUIPMENT. RESOLVE ALL DISCREPANCIES WITHOUT FURTHER COST TO OWNER.
14. FOR RETURN AIR PLENUMS, ALL MATERIALS LOCATED WITHIN A RETURN AIR PLENUM SHALL BE RATED AND APPROVED FOR INSTALLATION IN A RETURN AIR PLENUM.

ELECTRICAL LIGHTING CONTROL NOTES:

1. PARTIAL INTERIOR LIGHTS CONTROLLED BY MOTION SENSORS AS SHOWN, U.O.N..
2. TIMECLOCK TO BE INTERMATIC ET2845C SERIES WITH FOUR INDEPENDENT OUTPUTS AND HOLIDAY FUNCTION.
   TIME CLOCK FEATURES:
   A. 365-DAY PROGRAMMABLE CLOCK WITH 48 ON/48 OFF FEATURES.
   B. AUTOMATIC DAYLIGHT SAVING TIME (DST) ON/OFF ADJUSTMENT.
   C. NON-VOLATILE EEPROM MEMORY FOR LIFETIME PROGRAMMING PROTECTION.
   D. 100-HOUR SUPERCAPACITOR ELIMINATES BATTERY DEPENDENCY.
   E. 50 HOLIDAY BLOCKS WITH SCHEDULES.
3. PROVIDE INTERMATIC MODEL #EI235W 2-HOUR ELECTRONIC COUNTDOWN TIMER SWITCH IN PARALLEL CONNECTION FOR OVERRIDE WHERE NOTED.
4. PROVIDE CONTACTORS AS NEEDED.
5. CIRCUITS TO BE CONTROLLED BY TIMECLOCK OUTPUT WITH 2-HOUR TIMED OVERRIDE SWITCH:
   A-4
4. CIRCUITS TO BE CONTROLLED BY TIMECLOCK OUTPUT:
   A-12, A-16, A-36
5. CIRCUITS TO BE CONTROLLED BY PHOTOCELL RECEPTORS:
   A-6, A-8,10, B-27, B-29.

LEGEND OF ELECTRICAL SYMBOLS

SYMBOL	DESCRIPTION
	CONDUIT RUN CONCEALED IN WALLS OR ABOVE CEILING. ARROW INDICATES HOMERUN TO PANEL. CONDUCTOR DESIGNATIONS ARE AS FOLLOWS: LONG HATCH INDICATES NEUTRAL, SHORT HATCH INDICATES PHASE, "T" INDICATES INSULATED OR ISOLATED GROUND, "/" INDICATES SWITCHLEG, AND NO HATCHES INDICATES TWO CONDUCTORS.
	PARTIAL HOME RUN. SAME AS ABOVE.
	CONDUIT RUN CONCEALED IN FLOOR SLAB, BELOW FLOOR SLAB OR BELOW GRADE. WIRING SAME AS ABOVE.
	HATCHED LINES INDICATES FIXTURE CONNECTED TO BUILDING EMERGENCY CIRCUIT.
A	2'x4' FLUORESCENT FIXTURE. LETTER INDICATES FIXTURE TYPE. REFER TO LIGHTING FIXTURE SCHEDULE FOR SPECIFICATIONS.
A	2'x2' FLUORESCENT FIXTURE. LETTER INDICATES FIXTURE TYPE. REFER TO LIGHTING FIXTURE SCHEDULE FOR SPECIFICATIONS.
A	UNDERCABINET FIXTURE. LETTER INDICATES FIXTURE TYPE. REFER TO LIGHTING FIXTURE SCHEDULE FOR SPECIFICATIONS.
A	DOWNLIGHT FIXTURE. LETTER INDICATES FIXTURE TYPE. REFER TO LIGHTING FIXTURE SCHEDULE FOR SPECIFICATIONS.
A	WALL WASHER FIXTURE. LETTER INDICATES FIXTURE TYPE. REFER TO LIGHTING FIXTURE SCHEDULE FOR SPECIFICATIONS.
	EXIT LIGHT. PROVIDE ARROWS AS INDICATED ON DRAWINGS.
	DUPLEX RECEPTACLE OUTLET; 20 AMP, 125V., 3 WIRE, GROUNDED TYPE.
	QUADRUPLEX RECEPTACLE OUTLET GANGED WITH A COMMON WALL PLATE; (2)-20 AMP, 125V, 3 WIRE, GROUNDED TYPE.
GFI	DUPLEX RECEPTACLE OUTLET WITH GROUND FAULT INTERRUPTER; 20 AMP, 125V., 3 WIRE GROUNDED TYPE.
S D	FLUSH MOUNTED FLOOR OUTLET W/ RECEPTACLE (S) AND OR DATA AND, OR TELEPHONE.
	COMBINATION TELEPHONE / DATA OUTLET.
	TELEPHONE OUTLET.
	DATA OUTLET
TTB	TELEPHONE TERMINAL BOARD, 4'x8'x3/4" PLYWOOD.
$	SINGLE POLE, SINGLE-THROW SWITCH; 20 AMP, 120/277V.
3 $	3-WAY SWITCH: 20 AMP, 120/277V.
OS $	OCCUPANCY SENSOR SWITCH. LUTRON MS-B102, U.N.O.
VS $	VACANCY SENSOR SWITCH. LUTRON MS-B102, U.N.O.
	DIMMER SWITCH. LUTRON MAESTRO SERIES.
	JUNCTION BOX MOUNTED ABOVE ACCESSIBLE CEILING.
	JUNCTION BOX
	DISCONNECT IN A NEMA 1 ENCLOSURE, UNLESS OTHERWISE SPECIFIED. REFER TO DRAWINGS FOR AMPERAGE, PHASES, & FUSE SIZE. (IF REQUIRED)
	MOTOR STARTER / DISCONNECT IN A NEMA 1 ENCLOSURE, UNLESS OTHERWISE SPECIFIED. REFER TO DRAWINGS FOR AMPERAGE, PHASES, FUSE SIZE (IF REQUIRED), AND SIZE.
	TRANSFORMER - REFER TO DRAWINGS FOR VOLTAGE AND AMPERAGE.
	SURFACE PANELBOARD W/ NEC CLEARANCES; 120/208 VOLT.
	SURFACE PANELBOARD W/ NEC CLEARANCES; 277/480 VOLT.

NOTES: 1. ALL SYMBOLS MAY NOT BE USED ON THIS DRAWINGS.
2. REFER TO SPECIFICATIONS FOR MOUNTING HEIGHTS

WIRELESS LIGHT SWITCHING CONTROLS

SYMBOL	DESCRIPTION
a $	A SINGLE LEADER CORRESPONDS TO A SINGLE SWITCH FOR THAT LIGHTING CIRCUIT. THE SWITCH WILL HAVE A CORRESPONDING AND MATCHING DESIGNATION LETTER IF THERE ARE OTHER SWITCHES IN THE SAME ROOM.
a b $	MULTIPLE LEADERS CORRESPOND TO MULTIPLE SWITCHES FOR THAT LIGHTING CIRCUIT. THE QUANTITY OF LEADERS CORRESPONDS TO THE QUANTITY OF SWITCHES THAT CONTROL THAT CIRCUIT. THE SWITCHES WILL HAVE A CORRESPONDING AND MATCHING DESIGNATION LETTER.

LIGHTING CONTROL SCHEDULE

MARK	CONTROL DESCRIPTION	CONTROL DEVICES	SEQUENCE OF OPERATION
1	WALL MOUNTED VACANCY SENSING	MS-B102 (DUAL-TECHNOLOGY WALL VACANCY SENSOR)	LIGHT FIXTURES IN THIS ROOM ARE TO BE MANUAL-ON/ AUTO-OFF CONTROLLED BY THE WALL MOUNTED VACANCY SENSOR SWITCH.
1C	WALL MOUNTED OCCUPANCY SENSING	MS-B102 (DUAL-TECHNOLOGY WALL OCCUPANCY SENSOR)	LIGHT FIXTURES IN THIS ROOM ARE TO BE AUTO-ON/ AUTO-OFF CONTROLLED BY THE WALL MOUNTED OCCUPANCY SENSOR SWITCH.
2B	CEILING MOUNTED VACANCY SENSING	PJ2-2B-GXX-L01 (WIRELESS REMOTE SWITCH) LRF2-OCR2B-P (WIRELESS CEILING VACANCY SENSOR) RMJS-16R-DV-B (RELAY POWER PACK WITH WIRELESS RECEIVER)	LIGHT FIXTURES IN THIS ROOM ARE TO BE MANUAL-ON/ AUTO-OFF CONTROLLED BY THE RELAY POWER PACK WITH WIRELESS RECEIVER; RECEIVING INPUTS FROM THE WIRELESS CEILING MOUNTED VACANCY SENSOR & THE WIRELESS REMOTE SWITCH.
2C	CEILING MOUNTED OCCUPANCY SENSING	PJ2-2B-GXX-L01 (WIRELESS REMOTE SWITCH) LRF2-OCR2B-P (WIRELESS CEILING OCCUPANCY SENSOR) RMJS-16R-DV-B (RELAY POWER PACK WITH WIRELESS RECEIVER)	LIGHT FIXTURES IN THIS ROOM ARE TO BE AUTO-ON/ AUTO-OFF CONTROLLED BY THE RELAY POWER PACK WITH WIRELESS RECEIVER; RECEIVING INPUTS FROM THE WIRELESS CEILING MOUNTED OCCUPANCY SENSOR & THE WIRELESS REMOTE SWITCH.
3	WALL MOUNTED VACANCY SENSING WITH DIMMING	MRF2S-8SD010 (PIR WALL VACANCY SENSOR WITH 0-10V DIMMING)	LIGHT FIXTURES IN THIS ROOM ARE TO BE MANUAL-ON/ AUTO-OFF CONTROLLED BY THE WALL MOUNTED VACANCY SENSOR SWITCH WITH DIMMING CAPABILITIES.
4B	CEILING MOUNTED VACANCY SENSING WITH DIMMING	PJ2-2BRL-GXX-L01 (WIRELESS REMOTE SWITCH WITH DIMMING) LRF2-OCR2B-P (WIRELESS CEILING VACANCY SENSOR) RMJS-8T-DV-B (0-10V DIMMING POWER PACK WITH WIRELESS RECEIVER)	LIGHT FIXTURES IN THIS ROOM ARE TO BE MANUAL-ON/ AUTO-OFF CONTROLLED BY THE DIMMING POWER PACK WITH WIRELESS RECEIVER; RECEIVING INPUTS FROM THE WIRELESS CEILING MOUNTED VACANCY SENSOR & THE WIRELESS DIMMING REMOTE SWITCH.

THIS CONTROL SCHEDULE IS INTENDED TO PROVIDE GENERAL LIGHTING CONTROL DEVICE QUALITY AND PERFORMANCE REQUIREMENTS ONLY. CONTRACTOR SHALL BE RESPONSIBLE TO OBTAIN THE EXACT MODEL/CATALOG NUMBER OF THE LIGHTING CONTROL DEVICES LISTED ABOVE. THIS LIGHTING CONTROL DESIGN IS BASED ON LUTRON LIGHTING CONTROL DEVICES, CONTRACTOR MUST SUBMIT ANY SUBSTITUTION OF AN APPROVED MANUFACTURER TO THE ENGINEER FOR REVIEW.

LIGHTING FIXTURE SCHEDULE

TYPE	MANUFACTURER + SERIES NUMBER	MOUNTING	LAMPS NO/TYPE	VOLTS	REMARKS
A2	WILLIAMS P/N FT-24-LS-8CS-AF-DIM-UNV 39W@3500K	RECESSED	38.9W LED	120	RECESSED CENTER BASKET LED 2X4 TROFFER. 0-10V DIMMING.
A2E	WILLIAMS P/N FT-24-LS-8CS-AF-EM/10W-DIM -UNV 39W@3500K	RECESSED	38.9W LED	120	RECESSED CENTER BASKET LED 2X4 TROFFER. 0-10V DIMMING. PROVIDE 90 MINUTE BATTERY PACK.
A3	WILLIAMS P/N FT-24-LS-8CS-AF-DIM-UNV 27W@3500K	RECESSED	27.3W LED	120	RECESSED CENTER BASKET LED 2X4 TROFFER. 0-10V DIMMING.
A3E	WILLIAMS P/N FT-24-LS-8CS-AF-EM/10W-DIM -UNV 27W@3500K	RECESSED	27.3W LED	120	RECESSED CENTER BASKET LED 2X4 TROFFER. 0-10V DIMMING. PROVIDE 90 MINUTE BATTERY PACK.
DA	WILLIAMS P/N 4AR-L15/835-DIM-UNV-OM -OF-CS-N-F1	RECESSED	17.2W LED	120	4" RECESSED LED DOWNLIHGT. 3500K. 1500LM. 0-10V DIMMING.
DAE	WILLIAMS P/N 4AR-L15/835-EM/7W-DIM-UNV-OM -OF-CS-N-F1	RECESSED	17.2W LED	120	4" RECESSED LED DOWNLIHGT. 3500K. 1500LM. 0-10V DIMMING. PROVIDE 90 MINUTE BATTERY PACK.
D4	WILLIAMS P/N 4DR-TL-L10/835-DIM-UNV-OM -OF-CS-N-F1	RECESSED	9W LED	120	4" RECESSED LED DOWNLIHGT. 3500K. 1000LM. 0-10V DIMMING.
D4E	WILLIAMS P/N 4DR-TL-L10/835-EM/7W-DIM-UNV-OM -OF-CS-N-F1	RECESSED	9W LED	120	4" RECESSED LED DOWNLIHGT. 3500K. 1000LM. 0-10V DIMMING. PROVIDE 90 MINUTE BATTERY PACK.
D4B	WILLIAMS P/N 4DR-TL-L15/835-DIM-UNV-OM -OF-CS-N-F1	RECESSED	9W LED	120	4" RECESSED LED DOWNLIHGT. 3500K. 1500LM. 0-10V DIMMING.
G	WILLIAMS P/N 96-4-L62/835-HIAFR-DIM-UNV	SURFACE	48W LED	120	LINEAR LED LIGHT. 3500K. 0-10V DIMMING.
PD	KICHLER ABBOTSWELL 12 LIGHTS CHANDELIER (43498BK) - 39.25"	SUSPENDED	60W LED	120	DECORATIVE PENDANT LIGHT. 0-10V DIMMING.
PD	VISUAL COMFORT & Co. SLO1271TXB	SUSPENDED	19W LED	120	DECORATIVE HANGING LANTERN. TEXTURED BLACK.
UMI	VISUAL COMFORT & Co. SLO1221TXB	WALL	11.8W LED	120	DECORATIVE MINI WALL LANTERN.
D4X	WILLIAMS P/N 4DR-TL-L20/835-DIM-UNV-OW -OF-CS-WET-CC-N-F1	RECESSED	20W LED	120	4" RECESSED LED DOWNLIHGT. 3500K. 2000LM. 0-10V DIMMING. WET LOCATION.
SL	LSI P/N MRM-LED-18L-SIL-FT-UNV-DIM-30 -70CRI-XX	POLE	270W LED	120	PARKING LOT POLE LIGHT.
WM	LSI P/N XWM-4-LED-12L-40-UE-XX	WALL	77W LED	120	EXTERIOR WALL PACK.
FL	LSI P/N XFLM-MF-LED-28-HO-CW-UE	GROUND	36W LED	120	GROUND MOUNTED FLAG LIGHT.
DL	LSI P/N XIG	GROUND	19W LED	120	GROUND MOUNT LANDSCAPE AND DIRECTIONAL SIGN. LED. WET LOCATION.
X	LSI P/N EX-R-U-WB-WH	SURFACE	< 5W LED	120	NEW EXIT SIGN. PROVIDE WITH 90-MINUTE BATTERY PACK. MATCH DIRECTIONAL ARROWS AS NOTED ON PLANS.
EM2	LSI P/N SRL-D-BK	SURFACE	1.5W LED	120	DOUBLE HEAD LED REMOTE EMERGENCY LIGHT. WET LOCATION.

THIS FIXTURE SCHEDULE IS INTENDED TO PROVIDE GENERAL LIGHTING FIXTURE QUALITY AND PERFORMANCE REQUIREMENTS ONLY. CONTRACTOR SHALL BE RESPONSIBLE TO OBTAIN THE EXACT MODEL/CATALOG NUMBER OF THE LIGHTING FIXTURES LISTED ABOVE. ANY DIFFERENCES BETWEEN THIS LIGHTING FIXTURE SCHEDULE AND ARCHITECTURAL DRAWINGS OR MANUFACTURERS PRODUCT LISTINGS SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE ENGINEER. FLUORESCENT LIGHTS THAT ARE SHOWN WITH DIMMER CONTROL SHALL BE PROVIDED WITH AN ELECTRONIC DIMMING BALLAST. FLUORESCENT LIGHTS NOT SHOWN DIMMED SHALL HAVE A NON-DIMMING ELECTRONIC BALLAST. ALL LAMPS SHALL MATCH BUILDING STANDARD.

SLI GROUP, INC.
ARCHITECTURE | DESIGN | CONSTRUCTION
15810 PARK TEN PLACE, SUITE 300
HOUSTON, TEXAS 77084
713-465-4650
www.sligroup.com

© COPYRIGHT

National Bank & Trust - Bastrop
Enter address here
E/BE Project Number : 26129.00

ISSUED FOR CLIENT APPROVAL	DATE
ISSUED FOR BIDDING	09/11/26
ISSUED FOR PERMIT	09/11/26
ISSUED FOR CONSTRUCTION	11/02/26

REVISIONS

MARK	DESCRIPTION	DATE
	70% REVIEW SET	07/29/26
	90% REVIEW SET	08/20/26
	ISSUE FOR PERMIT & BID	09/11/26
	ADDENDUM A	09/18/26
	ADDENDUM B	09/24/26
	ADDENDUM C	10/07/26
	ADDENDUM F	10/30/26
	ISSUE FOR CONSTRUCTION	11/02/26

The information, ideas, designs, details, layouts, techniques, features, arrangements, plans, sequences, dimensions, allowances, tolerances, conceptions, specifications, intentions, technology or embodiments, as illustrated, arranged, displayed, noted, recorded, indicated, represented, disclosed, evidenced, detailed or otherwise reduced to tangible form hereon, either expressly, inherently or by implication, are the confidential and proprietary information of SLI Design, Inc., and shall not be used for any purpose other than the specific project or undertaking identified on the drawing title block or legend for which they are and have been prepared by SLI Design, Inc. Any other reproduction, disclosure or use of any portion of the confidential and proprietary information of SLI Design, Inc., shall be a breach of the obligation of confidence created by the acceptance of this drawing from SLI Design, Inc. for a specific project or Contract. Any copying, duplicating, reproducing, utilization, alteration, modification, revision or change to this drawing, is expressly prohibited unless done with the prior written consent or approval of SLI Design, Inc., and shall not be undertaken without receipt of such prior written approval. This drawing is loaned by SLI Design, Inc., for the limited purpose of complying with a specific Contract. The drawing remains the property of SLI Design, Inc., and shall be returned upon request or completion of the contract, unless specifically authorized by Contract, under which it was loaned.

STATE OF TEXAS
JOSE M. GUERRERO
154536
REGISTERED PROFESSIONAL ENGINEER
11/02/2026

DRAWING TITLE
ELECTRICAL INFORMATION

SHEET NO.
E-0.10

E/BE Mechanical Electrical Plumbing CONSULTING ENGINEERS
12603 Southwest Fwy, Ste 170, Stafford, Tx 77477
Tel: (713) 840-0177 / Firm Reg. No: 5638